



Case Study

Lift Pit Deck Melbourne

Modular Access Platforms

Providing the perfect fit on-site every time

Project

Lift Pit Deck, 380 Lonsdale Street, Melbourne VIC

Installer

Otis Australia

Products

KOMBI Modular Access Platforms

Situation

Welded steel platforms have traditionally been used for lift pit access. They require exact measurements to be provided for manufacture. Get those measurements wrong and the whole system may need to be re-fabricated.

Assembly in confined areas can cause additional issues including the problem of physically getting the heavy equipment into the location and then the use of hot welding works to install the units.

Otis Australia had struggled with their client's existing welded steel platform and when they required a simpler more modular solution they contacted SAYFA

Solution

Having found the previous steel platform system difficult to work with, KOMBI's modularity and lightweight aluminium construction was exactly what Otis and their client were looking for.

The access platforms / decks were tailored to suit the site conditions and with the ability to be adjusted in situ the stress of obtaining exact measurements was a thing of the past. Being modular, the KOMBI platform could be supplied in loose components and transported to the exact location by hand without the need for heavy lifting equipment - another important benefit when working in such small spaces.

Otis were able to install the access platform themselves using basic power tools, making any minor modifications as required using the patented KOMBI T-Bolt.

The quick and hassle free install has cemented KOMBI's modular benefits to the team at OTIS, notwithstanding the significant cost savings that they received by utilising their own staff for the assembly.



KOMBI
MODULAR ACCESS

SMARTER - EASIER - FASTER